BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2012-13/RD/WORK_INDENT4252/CALL-2

APPROVED SCHEDULE - B

[redacted]EE/BTP/BBMP/E-PMT/06/2014-15, Date: 01.09.2014

Providing cement concrete to roads in Ramachandrapura village in ward no 10

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of E RAMESHA ANAND	
				In Figures	In Words
1	1329	Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet / surface dressing and stacking of old serviceable materials by manual means including cost of all charges complete as per specifications. and directions of engineer in charge	Sqm	29.28	Rupees Twenty Nine and Twenty Eight Paise Only
2	132.9	KSRRB M300-53: Construction of embankment with approval material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) and directions of engineer in charge	Cum	130.0	Rupees One Hundred Thirty Only
3	199.35	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. and directions of engineer in charge	Cum	3700.0	Rupees Three Thousand Seven Hundred Only
4	132.9	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc.., complete (exclusive of cost of steel and fabrication chaerges) and directions of engineer in charge	Cum	4500.0	Rupees Four Thousand Five Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92